



भा.कृ.अ.प.- भारतीय कृषि अनुसंधान संस्थान
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE



क्षेत्रीय केन्द्र (खाधान एव उधान), अमरतारा काटेज, शिमला-171004

REGIONAL STATION (CEREALS AND HORTICULTURE CROPS)AMARTARA COTTAGE, SHIMLA-171004
Phone No. 0177-2655305,2808766

मि. सं. 1-64/2022-23/

दिनांक:13.05.2022

QUOTATION NOTICE

Item/percentage rate sealed Quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MC, Shimla, PWD or other Central/State Govt./Semi Govt. agencies or specialist of such work. The contractor must have valid IT-PAN/VAT/TIN registration number and having experience of two similar nature of works in last two years for the work mentioned below:

S.No.	Name of work	Estimated cost / Item Rate	Earnest Money	Time limit for completion of work
1.	Construction of Poly-house/poly-tunnel for Plant Pathology studies near new office cum laboratory building at IARI, RS, Amartara Cottage, Shimla-171004 in externally funded project	1.52 lakhs	2%	30days

Last date of Submission of quotation:

up to 14:30 hours of 06.06.2022

Opening of quotation:

15:00 hours of 06.06.2022

Desirous and eligible agencies to download the schedule and details may visit IARI website www.iari.res.in and deposit requisite EMD at the time of filing of Quotation. **The rates on schedule and requisite eligibility documents should be filled in separate envelopes submitted both together in a bigger envelope well before the last date** otherwise quotation will be rejected. The schedule of work can be obtained from office the Head, IARI, Amartara Cottage, Shimla on working day by producing the eligibility documents and depositing the earnest money in the form of PO/DD favouring "Head, IARI, Regional Station, Amartara Cottage Shimla -171004." The Head IARI, Shimla reserves the right to reject or accept any Quotation without assigning any reason. Quotations shall be submitted along with the eligibility documents and forwarding letter addressed to Head, IARI, RS, Shimla otherwise quotation will not be considered.

S.No.	Specification/Description of work	Quantity
	As per Annexure-1	1(One) Nos.

Head, RS, Shimla

Copy to:-

- Comptroller, Directorate, IARI, Pusa, New for kind information please.
- F. & A.O.(Audit-IV)
- AAO (Contingency).
- In-charge USI to display on website.(The Quotation Notice already sent to IARI web master)

Specification for poly-Tunnel/poly-house

Sr. No.	Structural specification	Dimension/size
1.	Dimension of poly-tunnel	10 X 5 m
2.	Side height	2.3M
3.	Centre height	3.8M
4.	Base post	40 mm (1.5") thickness 2.5 mm
5.	Truss	32MM (1.25") thickness 2.2 mm
6.	Runner and ridge	32 mm (1.25") thickness 2.2 mm
7.	Truss braces	25 mm (1.0") thickness 2.2 mm
8.	Purlin + Boundary	25 mm (1.0") thickness 2.2 mm
9.	Roll up pipe	15 MM (1/2") thickness 2.2 mm
10.	vertical post for monkey protection	32 mm (1.25") thickness 2.2 mm
11.	Truss for monkey protection	25mm thickness 2.2 mm
12.	Side purlin for monkey protection	25mm thickness 2.2 mm
13.	Curtain handle	15 mm thickness 2.2 mm
14.	Door	1
15.	Polysheet-200 Micron, UV Stabilized	200 Micron
16.	Insect NET UV stabilized	40 mesh, white colour
17.	Monkey protection net UV stabilized	4 X 4"
18.	Exhaust Fan with electricity control	18"
19.	Provision for protection against monkey	All around the poly-house/poly-tunnel with HDPE NET
20.	Warranty	Warranty for 3 years from the date of installation for structure including poly film and net (for all material and installation defects on pro-rata basis). The structure should resist harsh climate of Shimla including snow



भा.कृ.अ.प.- भारतीय कृषि अनुसंधान संस्थान
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE



क्षेत्रीय केन्द्र (खाधान एव उधान), अमरतारा काटेज, शिमला-171004

REGIONAL STATION (CEREALS AND HORTICULTURE CROPS)AMARTARA COTTAGE, SHIMLA-171004
Phone No. 0177-2655305,2808766

मि. सं. 1-64/2022-23/

दिनांक:13.05.2022

निविदा सूचना

निदेशक, भा.कृ.अनु.सं., नई दिल्ली की ओर से के.लो.नि.वि., एम.ई.एस., , एम.सी., एवं अन्म केंद्रीम/प्रदेश सरकार/अर्धसरकारी संस्थाओं के पंजीकृत निविदाकारों या इस काम विशेषज्ञों से निम्न कार्य के करा हेतु आईटवाईज रेटों की प्राप्ति हेतु शीलबंद दर निविदा आमंत्रित की जाती है ! ठेकेदारों के पास वैध-IT-PAN/VAT/TIN पंजीकरण प्रमाणपत्र तथा इस प्रकार के काम करने का दो वर्षों का अनुभव होना चाहिये ! किया जाने वाला कार्य का विवरण निम्न प्रकार से है:-

S.No.	Name of work	Estimated cost / Item Rate	Earnest Money	Time limit for completion of work
1.	Construction of Polyhouse/polytunnel for Plant Pathology studies near new office cum laboratory building at IARI, RS, Amartara Cottage, Shimla-171004 in externally funded project	1.52 lakhs	2%	30days

Last date of Submission of quotation:

up to 14:30 hours of 06.06.2022

Opening of quotation:

15:00 hours of 06.06.2022

इच्छुक एवं योग्य निविदाकार द्वारा इस कोटेशन को भा.कृ.अनु.सं. की वैबसाईट www.iari.res.in से विवरण को देखा तथा डाउनलोड भी किया जा सकता है! सूचिदर रेट व आवश्यक योग्यता दस्तावेज अलग-2 शीलबंद लिफाफे में निर्धारित ई.एम.डी. राशि पी.ओ./डी.डी. के रूप में जो कि "Head, IARI, Regional Station, Amartara Cottage, Shimla-171004" के नाम पर देय होना चाहिये में कोटेशन के साथ संलग्न होना चाहिये ! अन्यथा/कोटेशन पर विचार नहीं किया जायेगा ! कार्य का विवरण इस कार्यालय से प्रमुख, भा.कृ.अनु.सं., क्षेत्रीय केंद्र, शिमला से किसी भी कार्य दिवस को शुबह 10:00 बजे से 5:00 बजे तक अपनी पात्रता के कागजात दिखाकर प्राप्त किये जा सकते हैं ! प्रमुख, भा.कृ.अनु.सं., क्षेत्रीय केंद्र, शिमला को बिना कोई कारण बताये कोटेशन को स्वीकार या अस्वीकार करने का पूरा अधिकार होगा !

क्र.सं.	कार्य का विवरण	मात्रा
	अनुसंलग्नक-1	1(एक)

प्रमुख, क्षेत्रीय केंद्र, शिमला

Copy to:-

- लेखा नियंत्रक, भा.कृ.अ.सं., पूसा, नई दिल्ली-110 012 आवश्यक कार्यवाई हेतु !
- वित्त एवं लेखा अधिकारी (ऑडिट-IV) आवश्यक कार्यवाई हेतु ।
- सहा. प्रशा. अधिकारी (Contingency).
- प्रभारी, यू.एस.आई., भा.कृ.अनु.सं. पूसा, नई दिल्ली-110 012 को इस आग्रह के साथ कि इसे संस्थान की वैबसाईट पर अपलोड करवाने की कृपा करें !

Specification for poly-Tunnel/poly-house

Sr. No.	Structural specification	Dimension/size
1.	Dimension of poly-tunnel	10 X 5 m
2.	Side height	2.3M
3.	Centre height	3.8M
4.	Base post	40 mm (1.5") thickness 2.5 mm
5.	Truss	32MM (1.25") thickness 2.2 mm
6.	Runner and ridge	32 mm (1.25") thickness 2.2 mm
7.	Truss braces	25 mm (1.0") thickness 2.2 mm
8.	Purlin + Boundary	25 mm (1.0") thickness 2.2 mm
9.	Roll up pipe	15 MM (1/2") thickness 2.2 mm
10.	vertical post for monkey protection	32 mm (1.25") thickness 2.2 mm
11.	Truss for monkey protection	25mm thickness 2.2 mm
12.	Side purlin for monkey protection	25mm thickness 2.2 mm
13.	Curtain handle	15 mm thickness 2.2 mm
14.	Door	1
15.	Polysheet-200 Micron, UV Stabilized	200 Micron
16.	Insect NET UV stabilized	40 mesh, white colour
17.	Monkey protection net UV stabilized	4 X 4"
18.	Exhaust Fan with electricity control	18"
19.	Provision for protection against monkey	All around the poly-house/poly-tunnel with HDPE NET
20.	Warranty	Warranty for 3 years from the date of installation for structure including poly film and net (for all material and installation defects on pro-rata basis). The structure should resist harsh climate of Shimla including snow

