

अनुरक्षण एवं अभियांत्रिकी इकाई
MAINTENANCE & ENGINEERING UNIT
भाकूअनुप-भारतीय कृषि अनुसंधान संस्थान
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE
नई दिल्ली-१२
NEW DELHI-12.

No. 30-13/21-22/ME Unit

SHORT QUOTATION NOTICE

Date: 13-09-2021

Percentage rate sealed Short Quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. agencies. The contractor must have valid IT-PAN,VAT,TIN and service tax registration number and having experience of two similar nature of works in last three years for the work mentioned below :

S. N	Name of work	Estimated cost / Item Rate	Earnest Money
1.	Roof treatment, repair of water tank base and other misc. works in ATIC Building at IARI PUSA, New Delhi-12.	Rs. 2,40,531.00	Rs. 5,000.00

Last date for receipt of applications for sale of quotation : 20.09.2021
Submission of quotation : up to 14:30 hours of 21.09.2021
Opening of quotation : 15:00 hours of 21.09.2021
Desirous and eligible agencies to download the schedule and details may visit IARI website www.iari.res.in and deposit the fee of Rs. 150/- (non-refundable) along with requisite EMD at the time of filing of Quotation. The rates on schedule and requisite eligibility documents should be filed in a separate envelopes submitted both together in a bigger envelope in case the Quotation is downloaded from the net, else the Quotation will be rejected. The schedule of work can also be purchased on payment of Rs. 150/- (non-refundable) from Tender Cell of M.E.Unit, Directorate during office hours on any working day by producing the eligibility documents and depositing the earnest money in the form of PO/DD favoring "Director, IARI, New Delhi-12." The Director IARI reserves the right to reject or accept any Quotation without assigning any reason. Quotations shall be submitted along with forwarding letter addressed to Director IARI otherwise quotation will not be considered.

Asstt. Admn. Officer (Works)

Copy to:-

1. Comptroller Directorate for kind information please.
2. F. & A.O.(Audit-IV)
3. AAO (Contingency).
4. In-charge USI to display on website.(The Quotation Notice already sent to IARI web master)

**Roof treatment, repair of water tank base and other misc. works in ATIC building at IARI PUSA,
New Delhi-12.**

S.No.	Particular	Qty	Unit	Rate	Amount
1	Removing of old pointing on tile work in laid on roofs in cement mortar including stacking material within 50 metres lead.	550.00	sqm	10.00	5500
2	Pointing on tile brick work with cement mortar 1:3 (1 cement : 3 fine sand):				
	Flush/ Ruled/ Struck or weathered pointing	550.00	sqm	260.90	143495
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking outjoints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :				
	With cement mortar 1:4 (1 cement : 4 fine sand)	20.00	sqm	417.80	8356
4	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design :				
	In 75x75 mm deep chase	50.00	Rm	237.25	11863
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	0.40	cum	7809.25	3124
6	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	325.00	kg	101.75	33069
7	Providing sand stone slab for roofing and laying them in cement mortar 1 : 4 (1 cement : 4 coarse sand) over wooden karries or R.C.C. battens or structural steel sections (Karries or battens or structural steel sections to be paid separately), including pointing the ceiling joints with cement mortar 1:3 (1 cement : 3 fine sand) complete :				
	Red sand stone slab				
	40 to 50 mm thick	7.00	sqm	793.10	5552
8	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	2000.00	per litre	8.80	17600
9	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.				
a)	15 mm dia nominal bore	20.00	Rm	284.90	5698
b)	20 mm dia nominal bore	10.00	Rm	344.10	3441
10	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :				

	20 mm nominal bore	4.00	each	460.2	1841
11	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :				
a)	15 mm nominal bore	2.00	each	235.75	472
b)	20 mm nominal bore	2.00	each	261.15	522
TOTAL					240531

Subject to be following terms & conditions:-

1. The work shall be executed as per CPWD specifications.
2. Income Tax, work Tax & work cess as per norms shall be recovered from the bill.
3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
4. The work shall start within two days from the date of award and complete within twenty days failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum upto 10%.
5. All the materials, laboures, T&P etc. required will be arranged by the firms itself.
6. Any other item to be required at site to complete the work will be executed as per the lowest quoted rates.
7. The Director, IARI has the right to reject any or all the quotation/tenders without assigning any reason.

Percentage rate to be quoted above or below in figure:.....
 In words:.....

Name with stamp & Signature of the Agency:.....

I/C (W) & CTO S.T.A.(C)