

रख-रखाव एवं अभियांत्रिकी इकाई
भारतीय कृषि अनुसंधान परिषद
भारतीय कृषि अनुसंधान संस्थान
नई दिल्ली -12.

सं. 08-55/18-19/एमईयू .

दिनांक 23-10-2018

e-निवेदा सूचना

निवेदा, भा. कृ. अनु. सं., को और से एवद्वारा अधालोखत निवेदा, ला. नि. वा., एम. ई. एस., रेलवेज, एम. सी. डी., लान, या अन्य केंद्र / राज्य सरकार / अर्द्ध सरकारी एजेंसीयों के साथ पंजीकृत ठेकेदारों / एजेंसीयों व विशेषकृत एजेंसीयों से मुद्रा दर निवेदा आमंत्रित की जाती है। एजेंसीयों के पास पैन, वैट/ टैट तथा GST पंजीकरण से हाना आनवाय है। तथा निवेदाशत व हेतु दो अगले वर्षों में समान कार्यों का अनुभव होना चाहिए

क्र. सं.	कार्य का नाम	अनुमानित लागत	धराहर रा
1.	P/f of false ceiling and aluminium work in the division of Agricultural Extension at IARI PUSA N.D.-12.	Rs. 2,72,927.00	Rs. 6000.00

ई-निवेदा आतंम तिथि : 23-11-2018 को 14.30 बजे तक
ई-निवेदा खुलने का तिथि : 24-11-2018 को 15.00 बजे तक
निवेदा की व : रु. 500/- मात्र (अप्रतिदेय)
इच्छुक एवं पात्र एजेंसीयों निवेदा विवरण देखने के लिए तथा ई-निवेदा प्रस्तुत करने व
<http://eprocure.gov.in>

सहायक प्रशासनिक आ (निर्माण / एम. ई. यूनिट)

**MAINTENANCE & ENGINEERING UNIT
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE
NEW DELHI-12.**

No. 08-55/18-19ME Unit

Dated : 23-10-2018

e-TENDER NOTICE

Item rate sealed Quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. or Specialize agencies. The contractor must have valid IT-PAN/VAT/TIN and GST registration number and having experience of two similar nature of works in last two years for the work mentioned below :

S.N	Name of work	Estimated cost / Item Rate	Earnest Money
1.	P/f of false ceiling and aluminium work in the division of Agricultural Extension at IARI PUSA N.D.-12.	Rs. 2,72,927.00	Rs. 6000.00

Last date & time submission of e-tender processing : up to 14:30 hours of 23.11.18

Opening of e-tender : 15:00 hours of 24.11.18

Tender Fee : Rs. 500/- (Non-refundable)

Desirous and eligible agencies for details & submission to e-tender may visit <http://eprocure.gov.in>

Asstt. Admn. Officer (Works)

P/f of false ceiling and aluminium work in the division of Agricultural Extension at IARI PUSA N.D.-12.

S.No	Particular	Qty.	Unit	Rate	Amount
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
	For fixed portion				
	Powder coated aluminium (minimum thickness of powder coating 50 micron	150.00	kg	384.50	57675
2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber /neoprene gasket required (Fittings shall be paid for separately)				
	Powder coated aluminium (minimum thickness of powder coating 50 micron)	80.00	kg	444.90	35592
3	P/f ACP sheet in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge.				
	Pre-laminated particle board with decorative lamination on both sides	10.00	Sqm	866.60	8666
4	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge.(Cost of aluminium snap beading shall be paid in basic item):				
	With float glass panes of 5.50 mm thickness	10.00	sqm	1003.95	10040

5	<p>Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.</p>				
	<p>12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part I and laminated with white 0.16mm thick fire retardant PVC film on, the face side and 12micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit.</p>	160.00	sqm	993.15	158904
6	<p>Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :</p>				
	<p>Painting with aluminium paint of approved brand and manufacture to give an even shade .</p>				
	<p>Two or more coats on new work</p>	30.00	sqm	68.35	2051
TOTAL		272927			

Subject to be following terms & conditions:-

1. The work shall be executed as per CPWD specifications.
2. Income Tax, work Tax & work cess as per norms shall be recovered from the bill.
3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
4. The work shall start within seven days from the date of award and complete within 30 days failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum upto 10%.
5. All the materials, laboures, T&P etc. required will be arranged by the firms itself.
6. Any other item to be required at site to complete the work will be executed as per the lowest quoted rates.
7. GST will be paid extra as per the norms of ministry of finanace.
8. The Director, IARI has the right to reject any or all the quotation/tenders without assigning any reason.

Rate to be quoted above or below in figure on 'A' above:.....

In words:.....

Name with stamp & Signature of the Agency:.....

I/C (W& CTO)

T.A.(C)